



November 13, 2007 T19602-22 Tetra Tech Project No. 112C01017

Mr. Paul Welsh HAZMAT Coordinator Delaware Department of Transportation 800 Bay Road P.O. Box 778 Dover, Delaware 19903

Dear Mr. Welsh:

Subject: Summary of Test Pit Environmental Site Investigation Field Activities in Support of DelDOT's Bridge 1-503 on St. Anne's Church Road Project, Middletown, Delaware; DelDOT Contract

No. 25-071-01

This letter report summarizes the procedures and findings of the Phase II Environmental Investigation performed in support of DelDOT's Bridge 1-503 Replacement Project, Middletown, Delaware (Figure 1). This Phase II Environmental Investigation included excavating multiple test pits in the area of the proposed storm water retention pond. The goal of the test pitting work was to help further delineate the lateral and vertical extent of fill material in the wooded area located on the western portion of the former Middletown Landfill site. Due to the heavy vegetation found currently existing on this section of the property, no data was collected from the location where the proposed storm water retention pond is to be constructed, during the geophysical survey previously performed at the site.

TEST PIT EXCAVATION PROCEDURE

Tetra Tech subcontracted with Lewis Environmental Group to provide a track excavator and operator to install the test pits at locations specified by Tetra Tech's supervising environmental scientist at the site. A total of 17 test pits was dug at the site on October 23 and 24, 2007 (Figure 2). The location of these test pits were placed to either complete a basic grid pattern sampling scheme for the subject property or biased to any observed visual cues of historical dumping locations on the subject property. The locations of the test pits were surveyed by the supervising Tetra Tech environmental scientist using a Trimble Geo-Explorer 3 Global Positioning System with a 1-meter resolution. A summary of the coordinates for the test pit locations based on the Geographic Coordinate Systems 1984 World Geodetic Survey are included in Table 1.

The depth of each test pit varied from 2 to 16 feet below ground surface, based on visual observations of the supervising environmental scientist in the field. These visual observations were focused on identifying the presence of any fill material within each test pit location. The location, thickness, and depth of any fill material observed were recorded, along with all pertinent information regarding the interface between the fill materials and the native soils. Once native soils were observed in each of the 17 test pits, further excavation was halted to limit any cross-contamination of the shallow fill materials to deeper, native soils. No soil samples were collected for laboratory analyses at any of the test pit locations.



OBSERVATIONS AND LANDFILL DELINEATION

Copies of Tetra Tech's test pit logs are included with this letter report. Landfill material consisting of ash, broken glass bottles, terra-cotta pipe, and pieces of brick, was encountered at test pit locations TP-1, TP-3, TP-10, TP-11, TP-12, and TP-16 at depths of 0.5 to 1 foot below existing grade and at thicknesses ranging from 2 to 4.5 feet. The landfill material also appears to extend to the northwest into the wetland area adjacent to Deep Creek. No test pits were dug in the wetland area during this investigation.

The first native soil layer encountered consisted of orange, tan, and light brown, fine to medium grained sand with some gravel.

Based on the results of this field investigation, Tetra Tech was able to generate a map showing the approximate extent of landfill area at the site (Figure 3). Due to undetermined extent of landfill material along the northwestern section of the property, Tetra Tech cannot accurately estimate the volume of landfill material currently found on the DelDOT property.

CONCLUSIONS

This environmental site investigation confirmed the existence of landfill material on the subject DelDOT property where the proposed storm water retention pond is to be constructed. This landfill material was encountered at approximately 0.5 to 1 foot below the existing grade and 2 to 4.5 feet thick. The landfill material also appears to extend to the northwest into the wetland area adjacent to Deep Creek.

Sincerely,

ason Daliessio

Geologist

Christopher Geiger, P.G.

Project Manager

jp

Enclosures

N:\Projects\T19000\T19602 3yr Environmental Work\-22\Documents\Letter_report.doc



Source: Roads from DelDOT; Tax Parcel from New Castle Co.; Topo from USGS DLGs; USGS State and County Boundaries from National Atlas (nationalatlas.gov).



0 510 20 30 40 Miles

1:2,877,900








Figure 1
General Location
St. Annes Church Road/Bridge I-503 DelDOT Site
Middletown, New Castle County, DE

TetraTech, Inc. 240 Continental Drive, Suite 200 Newark, DE 19713 Phone: (302) 738-7551 Toll Free: (800) 452-0910 www.tetratech.com www.tetratech-de.com

This map is provided by Tetra Tech solely for display and reference purposes and is subject to change without notice. No claims, either real or assumed, as to the absolute accuracy or precision of any data contained herein are made by Tetra Tech, nor will Tetra Tech be held responsible for any use of this document for purposes other than which it was intended.



Source: Roads from DelDOT; Tax Parcel from New Castle Co.; Topo from USGS DLGs; USGS State and County Boundaries from National Atlas (national atlas.gov).




037.575 150 225 300 Feet 1:1,060

TetraTech, Inc. 240 Continental Drive, Suite 200 Newark, DE 19713 Phone: (302) 738-7551 Toll Free: (800) 462-0910 www.tetratech.com www.tetratech-de.com



This map is provided by Tetra Tech solely for display and reference purposes and is subject to change without notice. No claims, either real or assumed, as to the absolute accuracy or precision of any data contained herein are made by Tetra Tech, no will Tetra Tech be held responsible for any use of this document for purposes other than which it was intended.



TETRA TECH - TEST PIT LOG

Project Nam	e: St. Annes	Church		Project No.:112C01017							
	ation:Middleto										
Test Pit No.							Date Excavated: 10/23/200	7	Inspector: Jason Daliessio	,	
Contractor:l	ewis Environ	mental					Excavation Method: Track Excavator				
Surface Ele	vation (ft):Unk	nown					Groundwater Depth (ft): 8		Total Depth (ft): 10		
				Strata Depth							
Sample		Depth (ft	MAA				Description of Materials		Materials	Moisture	
Sample	Depth (ft)		ш.	0.0	To 0.5	Light br	own silty sand with moderate pebble cont	tent and fill	material (glass, brick)	D	
				0.5				toric di la lin	material (glass, arter)	D	
				-		Fill material (ash, glass bottles, terra-cotta pipe)				м	
				3.5		Orange to light brown medium-grained sand, clean, native					
		-		9.0	10.0	Yellow t	o orange fine grained sand with moderat	e rounded	coarse gravels	S	
		-		10.0		End of t	poring			+	
						-				+-	
							×			+-	
										+-	
										-	
					1,					ـ	
										_	
										_	
,											
Groundwater obse	Notes and comments Moisture codes: D-dry, M-moist, W-wet, S-saturated Groundwater observed at approximately 8' below ground surface. To limit cross-contamination with shallower fill material, deeper native soils were not disturbed during the test pit investigation.										
10 mm a033-2011	The state of the s		,								
Samples Collected Time Designation Time						esigna	ation				

TETRA TECH - TEST PIT LOG

						A TEOTI TEOTITI EGG				
Project Name: St. Annes Church Road/Bridge I-503 Project No.:112C01017										
Project Loc	cation:Middleto	own, De	laware							
Test Pit No.	.:2					Date Excavated: 10/23/2007 Inspector: Jason Daliessio				
Contractor:	Lewis Environ	ımental				Excavation Method: Track Excavator	à			
Surface Ele	evation (ft): Un	ıknown				Groundwater Depth (ft): Total Depth (ft):2				
	PID r				a Depth (ft)					
Sample	Sample Depth (ft)	Depth (ft	ЬРМ	From	То	Description of Materials	Moisture			
				0.0		Light brown silty sand with trace fill material (glass, brick)	D			
	FS			0.5			D			
12				2.0		End of boring				
					1-					
				\square						
			+							
		-	, , ²		\square					
			-		\vdash					
		.,			\longrightarrow					
					\vdash					
							<u> </u>			
77										
HT.			. "				٠.			
Notes and		ower fill ma				-dry, M-moist, W-wet, S-saturated not disturbed during the test pit investigation.				
		g F								
					-					
Samples Collected Time Designation Time Desig					De	esignation				
		—		-+						

TETRA TECH - TEST PIT LOG

			-			TECHT LOG					
Project Name: St. Annes Church Road/Bridge I-503 Project No.:112C01017											
Project Loc	ation:Middleto	wn, Del	aware								
Test Pit No.	:3					Date Excavated: 10/23/2007 Inspector: Jason Daliessio	ı				
Contractor:	_ewis Environ	mental				Excavation Method: Track Excavator					
Surface Ele	vation (ft):Unk	nown				Groundwater Depth (ft): Total Depth (ft):8					
PID readings					Depth						
Sample	Sample Depth (ft)	Depth (ft	Wdd	From	To	Description of Materials	Moisture				
Sample	Deptii (it)		L.	0.0		Light brown silty sand with trace fill material (glass, brick)	D				
				2.0		Rounded coarse gravels with trace fine-to-medium grained sands	D				
				5.0		Rounded coarse gravels with trace fine-to-medium grained sands	D				
						and black cobble (rounded coarse gravel conglomerates)					
				6.5	8.0	Light brown to orange fine-grained sand, clean, native	м				
				8.0	0.0	End of boring					
3				0.0		End of boring					
						and the second s					
	=										
						2					
	Service interest (12										
							1				
Notes and	comments		Moist	ure coo	les: D-	dry, M-moist, W-wet, S-saturated	L -				
Samples C Time	ollected Designat	tion	Tir	ne	De	signation	2				