Section	Note	Comments
100	THE STORAGE OF CONSTRUCTION EQUIPMENT AND MATERIAL WILL NOT BE ALLOWED IMMEDIATELY ADJACENT TO RESIDENTIAL DWELLING OR COMMERCIAL BUILDING UNLESS PERMISSION IS GRANTED BY THE PROPERTY OWNER. LOCATION OF STORAGE AND LAY DOWN AREAS IS THE CONTRACTORS RESPONSIBILITY, SUBJECT TO THE APPROVAL OF THE ENGINEER.	This note has been deleted because it is partly covered by Section 106.07 of the specifications, the rest of this note is too restrictive and should not be used.
100	THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AN AREA SUITABLE FOR STOCKPILING BORROW, TOPSOIL AND OTHER FILL MATERIAL REQUIRED FOR THE PROJECT IN ACCORDANCE WITH SECTIONS 110.07 AND 110.10 OF THE STANDARD SPECIFICATIONS. SUBJECT TO THE APPROVAL OF THE ENGINEER, STOCKPILE AREA MAY BE LOCATED OUTSIDE THE PROJECT LIMITS, IF NECESSARY. NO ADDITIONAL PAYMENT WILL OCCUR FOR OFFSITE STOCKPILING.	This note has been deleted because it has been incorporated into Section 110.07 and 110.10 of the specifications.
100	ROADSIDE AMENITIES WITHIN THE LIMITS OF CONSTRUCTION OR EASEMENT AREAS THAT ARE TO REMAIN IN PLACE AND ARE NOTED BY "DND" SHALL BE PROTECTED BY THE CONTRACTOR WITH SAFETY FENCE OR OTHER MEASURES. ANY DAMAGE TO THESE AMENITIES SHALL BE REPAIRED IN KIND AT THE CONTRACTORS EXPENSE. PAYMENT FOR SAFETY FENCE WILL BE MADE UNDER ITEM 727520-CONSTRUCTION SAFETY FENCE.	This note has been deleted because it has been incorporated into Section 201.03 and 201.10 of the specifications.
100	THE CONTRACTOR IS SOLELY RESPONSIBLE TO OBTAIN OFF-SITE SPOIL AREAS FOR DISPOSAL OF EXCESS AND/OR UNSUITABLE MATERIALS AS NECESSARY, IN ADDITION TO THE REQUIREMENTS OF SECTION 106.09 OF THE STANDARD SPECIFICATIONS. OFF-SITE SPOIL AREAS MUST BE SUBMITTED TO THE DEPARTMENT FOR REVIEW AND APPROVAL BY DELDOT AND THE STATE HISTORIC PRESERVATION OFFICE PRIOR TO UTILIZATION BY THE CONTRACTOR. NO AREAS DESIGNATED AS WETLANDS WILL BE PERMITTED FOR USE AS DISPOSAL SITES. THE DEPARTMENT WILL NOT CONSIDER ANY DELAYS OR MONETARY CLAIMS OF ANY NATURE RESULTING FROM THE CONTRACTORS FAILURE OR DIFFICULTY IN FINDING NECESSARY DISPOSAL SITES TO MEET THE TIME FRAMES AND CAPACITIES REQUIRED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PLANS, PERMITS, EROSION AND SEDIMENT CONTROL MEASURES, ETC. REQUIRED BY THE APPROPRIATE REGULATORY AGENCIES FOR UTILIZING OFF-SITE SPOIL AREAS. THE CONTRACTOR SHALL CERTIFY TO THE ENGINEER THAT ALL REQUIRED PERMITS HAVE BEEN OBTAINED PRIOR TO UTILIZING THE OFF-SITE SPOIL AREAS. ALL COSTS FOR PROCURING AND UTILIZING THE OFF-SITE SPOIL AREAS ARE TO BE INCLUDED IN THE VARIOUS CONTRACT ITEMS GENERATING THE SPOIL MATERIALS. THIS NOTE SHALL ALSO APPLY TO EXISTING SUITABLE MATERIAL TO BE STOCKPILED EITHER ON-SITE OR OFF-SITE.	This note has been deleted because it has been incorporated into Section 106.09 of the specifications.
100	ANY DAMAGE TO ITEMS NOTED TO BE RELOCATED OR RESET BY THE CONTRACTOR, AT THE DISCRETION OF THE ENGINEER, SHALL BE REPAIRED AND/OR REPLACED IN KIND AT THE CONTRACTOR'S EXPENSE.	Approved for use. **(Cell PN_100_02)**
100	ALL FIRE HYDRANTS WITHIN THE LIMITS OF CONSTRUCTION SHALL REMAIN ACCESSIBLE AND OPERATIONAL AT ALL TIMES. IT IS THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT THE FINISHED GRADE AROUND EACH HYDRANT MAINTAINS A MINIMUM OF 18 INCHES FROM THE FINISHED GRADE TO THE HORIZONTAL VALVE ON THE HYDRANT.	This note has been deleted because it has been incorporated into Section 107.04 of the specifications.
200	THE CONTRACTOR SHALL REMOVE AND RESET ALL MAILBOXES TO MAINTAIN MAIL SERVICE AS DIRECTED BY THE ENGINEER. THE COST SHALL BE INCIDENTAL TO THE UNIT PRICE BID FOR ITEM 201000 - CLEARING AND GRUBBING.	This note has been deleted and replaced by the expanded version of the note included within this section.
200	THE CONTRACTOR SHALL REMOVE AND RESET ALL MAILBOXES TO MAINTAIN MAIL SERVICE AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL RELOCATE MAILBOXES AS REQUIRED BY THE PROPOSED GEOMETRICS AND AS DIRECTED BY THE ENGINEER. WHEN RELOCATING MAILBOXES IN CURBED SECTIONS, THE FACE OF THE MAILBOX SHALL BE FLUSH WITH THE BACK EDGE OF CURB. WHEN RELOCATING MAILBOXES IN OPEN SECTIONS, THE FACE OF THE MAILBOX SHALL SET BACK 8 INCHES FROM THE EDGE OF THE PAVED SHOULDER. THE BOTTOM OF THE MAILBOX SHALL BE SET 46 INCHES ABOVE THE ROADWAY SURFACE. MAILBOXES LOCATED AT DRIVEWAY ENTRANCES SHALL BE PLACED ON THE FAR SIDE OF THE DRIVEWAY IN THE DIRECTION OF TRAVEL. POSTS BEING RESET IN CONCRETE SIDEWALK SHALL BE PLACED IN AN APPROPRIATE SIZE PVC SLEEVE. COST FOR ALL WORK AND MATERIALS SHALL BE PAID UNDER ITEM 201000 – CLEARING AND GRUBBING.	Approved for use. **(Cell PN_200_02)**
200	ALL TREES, STUMPS, AND ROOTMAT REMOVED UNDER 201000 SHALL BE ENTIRELY REMOVED REGARDLESS OF DEPTH. BURIAL OF ORGANIC MATTER WITHIN THE PROJECT LIMITS IS NOT PERMITTED. OPEN BURNING OF TREES, STUMPS, BRUSH, ETC. IS NOT PERMITTED. CHIPPED MATERIAL MUST BE REMOVED PRIOR TO PLACING EMBANKMENT OR TOPSOIL.	This note has been deleted because it has been incorporated into Section 201 of the specifications.
200	IN AREAS WHERE TREES OR SHRUBS WILL BE OVERHANGING THE PROPOSED SIDEWALK, PRUNING MAY BE NECESSARY TO ACHIEVE A VERTICAL CLEAR SPACE OF 10 FEET ABOVE THE PROPOSED SIDEWALK ELEVATION. THE CONTRACTOR SHALL PRUNE EXISTING TREE AND SHRUB BRANCHES, WHICH OVERHANG THE SIDEWALK, IN ACCORDANCE WITH I.S.A. STANDARDS. THE CONTRACTOR SHALL NOTIFY DELDOT'S ROADSIDE ENVIRONMENTALIST ADMINISTRATOR, EUGENE 'CHIP' ROSAN, JR. (302) 760-2185 AND/OR HIS DESIGNEE, AT LEAST TWO (2) DAYS PRIOR TO THE PRUNING OPERATION. ALL COSTS ASSOCIATED WITH THE ABOVE WORK TO BE PAID UNDER ITEM 201000 – CLEARING AND GRUBBING.	Approved for use. **(Cell PN_200_03)**
200	THE CONTRACTOR SHALL PROTECT TREES NOTED ON THE PLANS BY"DND" WITH CONSTRUCTION SAFETY FENCE ERECTED AT THE DRIP LINE OF THE TREES. PAYMENT TO PROTECT TREES WILL BE MADE UNDER ITEM 727520 - CONSTRUCTION SAFETY FENCE.	This note has been deleted because it has been incorporated into Section 201.03 of the specifications.
200	THE ENGINEER MAY REQUIRE THE CONTRACTOR TO EXCAVATE TEST PITS ALONG PROPOSED DRAINAGE RUNS, AT POINTS OF POSSIBLE UTILITY CONFLICTS, TO DETERMINE IF A CONFLICT EXISTS. ANY CONFLICTS SHALL BE COORDINATED BY THE CONTRACTOR, WITH THE ENGINEER AND THE UTILITY COMPANY INVOLVED. THE ENGINEER SHALL ULTIMATELY DETERMINE THE SOLUTION TO THE UTILITY CONFLICT. TEST HOLES SHALL BE MEASURED AND PAID FOR IN ACCORDANCE WITH ITEM 208000, BUT ONLY TO THE ACTUAL DEPTH EXCAVATED.	Note: A new item is being created for test holes and will eliminate the need for this note. Please check the Design Resource Center (DRC) for updated notes prior to advertisement. **(Cell PN_200_04)**

200	~~EXISTING PROPERTY MONUMENTS THAT ARE DISTURBED OR DESTROYED DURING CONSTRUCTION SHALL BE LOCATED AND SET BY, OR UNDER THE SUPERVISION OF, A REGISTERED PROFESSIONAL ENGINEER OR LAND SURVEYOR LISCENSED TO PRACTICE IN THE STATE OF DELAWARE. WHEN REPLACING DISTURBED OR DESTROYED MONUMENTS THE CONTRACTOR SHALL UTILIZE NEW MONUMENTATION OF COMPARABLE MATERIAL AND SIZE TO THE ORIGINAL MONUMENT WHICH MEET CURRENT STANDARDS FOR MONUMENTATION. THIS ALSO HOLDS TRUE FOR THE SETTING OF MONUMENTATION AT THE INTERSECTIONS OF NEW RIGHT OF WAY LINES AND PROPERTY LINES. PROPERTY MARKERS NOT INDICATED ON THE PLANS TO BE RELOCATED SHALL BE PROTECTED IN ACCORDANCE WITH SECTION 107.09 OF THE STANDARD SPECIFICATIONS.~~	This note has been deleted because it has been incorporated into Section 107.09 of the specifications.
200	~~ALL DRAINAGE PIPES AND DRAINAGE INLETS SCHEDULED FOR REMOVAL SHALL BE PAID FOR UNDER ITEM 202000-EXCAVATION AND EMBANKMENT, REGARDLESS OF DEPTH.~~	This note has been deleted because it has been incorporated into Section 202.04 of the specifications.
200	~~BORROW TYPE A SHALL BE USED TO BACKFILL ALL UNDERCUT AREAS AS DIRECTED BY THE ENGINEER.~~	This note has been deleted because specification 212.05 already addresses this issue. Specification 212.05 requires the contractor to follow Section 202 when preparing the area that has been undercut.
200	~~ALL CAVITIES FORMED BY THE REMOVAL OF EXISTING OR TEMPORARY CONCRETE FOUNDATIONS FOR POLE BASES AND CABINET BASES SHALL BE BACKFILLED AND PAID UNDER ITEM 209003-BORROW TYPE 'C'.~~	This note has been deleted because specifications 211 and 202 already address the issue regarding the backfilling of cavities.
200	ITEMS TO BE REMOVED UNDER ITEM 211000 - REMOVAL OF STRUCTURES AND OBSTRUCTIONS SHALL INCLUDE, BUT NOT BE LIMITED TO THE FOLLOWING: (A list of items should follow)	Approved for use. **(Cell PN_200_05)**
200	THIS PROJECT IS COVERED UNDER AN NPDES GENERAL PERMIT FOR CONSTRUCTION. UNDER THE GENERAL PERMIT, COMPLIANCE WITH DELDOT'S APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLANS WILL CONSTITUTE COMPLIANCE WITH THE NPDES INDUSTRIAL PERMITTING REQUIREMENTS FOR THIS CONSTRUCTION PROJECT. A COPY OF THE NPDES GENERAL PERMIT AND NOI IS KEPT ON FILE IN EACH OF THE CONSTRUCTION OFFICES AND THE DEPARTMENT'S TEAM SUPPORT SECTION. A COPY OF THE GENERAL PERMIT OR THE NOI CAN BE OBTAINED UPON REQUEST FROM EITHER THE DEPARTMENT'S STORMWATER ENGINEER OR THE APPROPRIATE CONSTRUCTION ENGINEER.	Approved for use. This project note should be used on all projects which involve disturbing 5,000 SF or more of land. **(Cell PN_200_06)**

300	A. THE CONTRACTOR MAY ELECT TO USE ANY OF THE FOLLOWING MATERIALS TO MEET THE REQUIREMENTS OF ITEM 302007 - GRADED AGGREGATE BASE COURSE, TYPE 'B': a. CRUSHED STOME (PER STANDARD SPECIFICATION 821) b. CRUSHED CONCRETE (PER STANDARD SPECIFICATION 821) c. HOT-MIX MILLINGS (PER SPECIAL PROVISION 302514 MILLED HOT-MIX BASE COURSE) THE CONTRACTOR WILL NOT BE ALLOWED TO MIX DIFFERENT MATERIALS (OR SIMILAR MATERIALS FROM DIFFERENT SOURCES) TO MEET THE REQUIREMENTS OF ITEM 302007 - GRADED AGGREGATE BASE COURSE, TYPE 'B'. ALL OF THE ABOVE LISTED MATERIALS ARE PERMITTED FOR USE ON THE JOB, PROVIDED THEY ARE SEPERATED INTO APPROVED AREAS. EACH AREA OF BASE COURSE MUST BE CONSTRUCTED USING MATERIALS FROM A SINGULAR SOURCE, FULL DEPTH, IN ORDER THAT PROPER TESTING MAY BE ACCOMPLISHED. THE CONTRACTOR AND DELDOT'S PROJECT ENGINEER SHALL AGREE ON THE LIMITS OF EACH SOURCE OF MATERIAL PRIOR TO PLACEMENT. B. THE QUANTITY USED FOR BASE OF EACH OF THE ABOVE LISTED MATERIALS WILL BE THE CONTRACTOR'S CHOICE, WITH THE TOTAL MEETING THE ADVERTISED QUANTITY OF ITEM 302007 - GRADED AGGREGATE BASE COURSE, TYPE 'B'. C. THE CONTRACTOR MAY ALSO ELECT TO RECYCLE MILLINGS FOR USE IN HOT-MIX AS PERMITTED BY THE STANDARD SPECIFICATIONS. THE CHOICE OF THE QUANTITY OF MILLINGS USED FOR THIS PURPOSE, OR FOR BASE COURSE, LIES WITH THE CONTRACTOR. ALL MILLING MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR. D. HOT-MIX MILLINGS MAY BE GENERATED FROM THE FOLLOWING SOURCES: a. MATERIAL MADE AVAILABLE WHEN MILLED ON THIS CONTRACT UNDER ITEM 760502. b. MATERIAL MILLED ON THIS CONTRACT AT THE CONTRACTOR'S CHOICE UNDER ITEM 202000. c. MILLED MATERIAL FURNISHED ON THE JOB FROM THE CONTRACTOR'S YARD OR OTHER OUTSIDE SOURCE. ALL MILLED MATERIALS SHALL MEET THE MATERIAL REQUIREMENTS OF ITEM 302514 MILLED HOT-MIX BASE COURSE. E. PAYMENT CLARIFICATION: a. SHOULD THE CONTRACTOR ELECT TO MILL PORTIONS OF HOT-MIX SHOWN ON THE PLANS TO BE REMOVED UNDER ITEM 202000 - EXCAVATION AND EMBANKMENT THE COST OF MILLING THIS HOT-MIX WILL BE PAID AS ITEM 202000 EXCAVATION AND EMBANKMENT. THE MILLINGS GENERATED MAY BE RECYCLED INTO HOT-MIX, UTILIZED FOR BASE COURSE, OR DISPOSED OF TO AN APPROVED SITE. HAULING COSTS FOR DISPOSAL AND/OR RECYCLING ARE INCIDENTAL TO ITEM 202000 - EXCAVATION AND EMBANKMENT. b. MILLINGS GENERATED UNDER ITEM 760502 - PAVEMENT MILLINGS, TAPERCUT MAY BE RECYCLED INTO HOT-MIX, UTILIZED FOR BASE COURSE OR DISPOSED OF BY THE CONTRACTOR TO AN APPROVED SITE. NO SEPARATE PAYMENT WILL BE MADE FOR TRANSPORTING MILLINGS ON SITE OR TO AN APPROVED DISPOSAL SITE. c. SHOULD THE CONTRACTOR ELECT TO TEMPORARILY STOCKPILE MILLINGS ON THE JOB SITE FOR LATER USE, ALL COSTS FOR STOCKPILING AND SUBSEQUENT REHANDLING SHALL BE INCIDENTAL TO ITEM 202000 - EXCAVATION AND EMBANKMENT. d. MILLINGS USED FOR BASE COURSE SHALL BE PLACED IN ACCORDANCE WITH THE REQUIREMENTS OF SPECIAL PROVISION 302514 - MILLED HOT-MIX BASE COURSE. NO SEPARATE PAYMENT WILL BE MADE TO FURNISH MILLINGS FROM AN OUTSIDE SOURCE OR TRANSPORT MILLINGS WITHIN THE PROJECT LIMITS. MILLINGS USED FOR BASE COURSE WILL BE PAID IN PLACE AT THE UNIT BID PRICE FOR ITEM 302007 - GRADED AGGREGATE BASE COUSRE, TYPE 'B'. e. ALL COSTS TO UTILIZE MILLINGS IN RECYCLED HOT-MIX WILL BE INCIDENTAL TO THE UNIT PRICE BID FOR THE HOT-MIX ITEM USING THE RECYCLED MATERIAL. f. SPECIAL PROVISION 302514 MILLED HOT-MIX BASE COURSE IS PROVIDED TO SPECIFY THE MEANS OF LAY DOWN AND COMPACTION AS WELL AS THE MATERIAL REQUIREMENTS FOR MILLINGS USED AS BASE COURSE. ALL COSTS TO BRING THE MILLINGS INTO COMPLIANCE WITH THE REQUIREMENTS OF 302514 MILLED HOT-MIX BASE COURSE ARE INCIDENTAL TO ITEM 302007 - GRADED AGGREGATE BASE COURSE, TYPE 'B'. NO PAYMENT WILL BE MADE FOR ITEM 302514 - MILLED HOT-MIX BASE COURSE. THE QUANTITY OF MILLINGS USED	Approved for use. This note should only be used on projects that have the potential for reuse of the hot-mix material as millings. **(Cell PN_300_02)**
400	THE PAVEMENT SECTION FOR HOT-MIX RESIDENTIAL DRIVEWAYS SHALL BE 2" HOT-MIX, TYPE 'C' OVER 8" GRADED AGGREGATE BASE COURSE, TYPE 'B', UNLESS OTHERWISE NOTED ON THE PLANS.	Approved for use. **(Cell PN_400_02)**
600	THE DEPARTMENT AND THE CONTRACTOR SHALL INSPECT ALL EXISTING PIPES AND DRAINAGE STRUCTURES TO BE USED IN THE FINAL DRAINAGE SYSTEM AND AGREE ON THE CONDITION PRIOR TO THE STRAT OF CONSTRUCTION. EXISTING PIPES AND DRAINAGE STRUCTURES DAMAGED DUE TO CONTRACTOR OPERATIONS SHALL BE REPAIRED OR REPLACED IN-KIND AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR IS REQUIRED TO VIDEO INSPECT NEW PIPE RUNS TO CONFIRM CONDITION PRIOR TO ACCEPTANCE. PAYMENT FOR VIDEO INSPECTION OF NEW PIPES WILL BE MADE UNDER ITEM 612529 - VIDEO INSPECTION.	Approved for use. **(Cell PN_600_02)**

600	~~CONSTRUCTION OF ANY PROPOSED DRAINAGE, TEMPORARY DRAINAGE, OR INSTALLATION OF EROSION CONTROL MEASURES SHALL START AT THE OUTFALL AND PROGRESS UPSTREAM FOR ALL CONSTRUCTION PHASES.~~	This note has been deleted because specification 612.08 already addresses this issue.
700	IN AREAS WHERE PROPOSED CURB MEETS EXISTING CURB AND THE TWO CURB TYPES ARE NOT SIMILAR, THE PROPOSED CURB SHALL BE TRANSITIONED IN 10 LINEAR FEET, UNLESS OTHERWISE DIRECTED BY THE ENGINEER. PAYMENT FOR THIS WORK, INCLUDING SAW CUTTING EXISTING CURB SHALL BE INCIDENTAL TO THE PROPOSED CURB ITEM.	Approved for use. **(Cell PN_700_02)**
700	WHERE PROPOSED CONCRETE SIDEWALK IS CONSTRUCTED TO MEET EXISTING SIDEWALK, THE EXISTING SIDEWALK SHALL BE SAWCUT AT THE TIE-IN POINT OR MEET THE NEAREST EXISTING SIDEWALK JOINT. ALL SAW CUTTING SHALL BE FULL DEPTH, UNLESS OTHERWISE NOTED ON THE PLANS OR DIRECTED BY THE ENGINEER AND SHALL BE PAID FOR UNDER ITEM 762002 – SAWCUTTING, CONCRETE, FULL DEPTH.	Approved for use. **(Cell PN_700_03)**
700	PORTLAND CEMENT CONCRETE CHANNELIZING ISLANDS THAT ARE LESS THAN 75 SQ FT MAY BE POURED MONOLITHICALLY, OR AS DIRECTED BY THE ENGINEER.	Approved for use. **(Cell PN_700_04)**
700	~~DRAINAGE STRUCTURES FOR NEW STORM DRAIN SYSTEMS MAY BE PRECAST OR CAST-IN-PLACE. CAST-IN-PLACE CONSTRUCTION MUST BE USED FOR DRAINAGE STRUCTURES THAT TIE INTO EXISTING SYSTEMS. SHOP DRAWINGS AND DESIGN CALCULATIONS SHALL BE SUBMITTED FOR APPROVAL FOR ALL CAST-IN-PLACE DRAINAGE STUCTURES. SHOP DRAWINGS ARE NOT REQUIRED FOR PRECAST OR CAST-IN-PLACE STRUCTURES THAT MATCH STANDARD CONSTRUCTION DETAILS.~~	This note has been deleted because it has been incorporated into Section 708.10 of the specifications.
700	STATION AND ELEVATION DATA GIVEN FOR DRAINAGE STRUCTURES ARE TO BE APPLIED TO THE CENTER OF THE GRATE FOR INLETS, AND TO THE CENTER OF THE STRUCTURE FOR JUNCTION BOXES AND MANHOLES.	Approved for use. **(Cell PN_700_05)**
700	DRAINAGE INLET GRATES ADJACENT TO THE ROAD, WITHIN THE PROJECT LIMITS, WHICH ARE NOT TYPE 1 SHALL BE REPLACED. THE ACTUAL LOCATIONS, THE NEED FOR ANY GRATE MODIFICATIONS OR FOR NEW FRAMES SHALL BE DETERMINED BY THE ENGINEER. ALL REPLACED GRATES/FRAMES SHALL BE DELIVERED TO THE NEAREST DISTRICT MAINTENANCE YARD WITH THE COST OF DELIVERY INCIDENTAL TO ITEM 708500 - REPLACING CATCH BASIN GRATES. FINAL PAYMENT FOR REPLACED GRATES/FRAMES SHALL NOT BE MADE UNTIL RECEIPT OF DELIVERED MATERIALS IS PRODUCED, SIGNED BY A DELDOT MAINTENANCE YARD SUPERVISOR.	Approved for use. **(Cell PN_700_06)**
700	THE NEW CASTLE COUNTY DEPARTMENT OF PUBLIC WORKS SHALL SUPPLY AND THE STATE'S CONTRACTOR SHALL INSTALL NEW SELF SEALING MANHOLE FRAMES AND COVERS ON ALL COUNTY SEWER MANHOLES, THAT ARE NOT BEING RELOCATED, WITHIN THE PROJECT LIMITS IN ACCORDANCE WITH THE COUNTY'S STANDARD SPECIFICATIONS. THE EXISTING MANHOLE FRAMES AND COVERS THAT ARE REMOVED SHALL BECOME THE PROPERTY OF THE STATE'S CONTRACTOR. PAYMENT SHALL BE INCIDENTAL TO ITEM 710506 - ADJUST AND REPAIR EXISTING SANITARY SEWER MANHOLE.	Approved for use. This project note should be used only on New Castle County projects where sanitary sewer manholes are within the project limits. **(Cell PN_700_07)**
700	~~PERTAINING TO THE MILLING OPERATIONS, THE REMOVAL AND CLEANUP OF THE HOT MIX RESIDUE WEDGE LEFT FROM THE MILLING OPERATIONS ALONG CURB LINES, ADJACENT TO SPEED HUMPS, ACROSS INTERSECTING STREETS, AND AT THE BEGINNING AND ENDING POINTS OF THE MILLING OPERATION, SHALL BE INCIDENTAL TO THE MILLING ITEM.~~	This note has been deleted because it has been incorporated into Section 760.04 of the specifications.
700	THE CONTRACTOR SHALL DELIVER ALL MILLED MATERIAL TO THE DELAWARE DEPARTMENT OF TRANSPORTATION'S **(Fill in yard name)** MAINTENANCE YARD. THE MATERIAL SHALL BE NEATLY STOCKPILED AT THE YARD. COSTS FOR THIS WORK SHALL BE INCIDENTAL TO ITEM 760000 - PAVEMENT MILLING, HOT-MIX.	Approved for use. The designer shall contact the appropriate district Maintenance Engineer to determine if the millings are wanted and the location where they are to be delivered. **(Cell PN_700_08)**
700	ALL PAVED AREAS TO BE RECONSTRUCTED OR WIDENED SHALL BE SAWCUT AT THE POINT WHERE THE NEW PAVEMENT IS TO TIE INTO THE EXISTING PAVEMENT.	Approved for use. **(Cell PN_700_09)**
700	ALL HOT-MIX SAW CUTTING SHALL BE FULL DEPTH, UNLESS OTHERWISE NOTED ON THE PLANS, OR AS DIRECTED BY THE ENGINEER.	Approved for use. **(Cell PN_700_10)**
Misc.	THE CONTRACTOR SHALL CONTACT MICHAEL ELLER, THE CHIEF OF SCHEDULING FOR DART FIRST STATE, 14 DAYS PRIOR TO THE START OF CONSTRUCTION AT 302-576-6061.	Approved for use. **(Cell PN_MISC_02)**
Misc.	CROSS SECTIONS USED IN THE PREPARATION OF THIS CONTRACT ARE AVAILABLE FROM THE DEPARTMENT.	Approved for use. **(Cell PN_MISC_03)**

Misc.	RIGHT-OF-WAY PLANS FOR RIGHT-OF-WAY OR EASEMENT STAKEOUT PURPOSES ARE AVAILABLE FROM THE DEPARTMENT.	Approved for use. **(Cell PN_MISC_04)**
Misc.	~~SEE ENVIRONMENTAL COMPLIANCE PLANS FOR ENVIRONMENTAL RESTRICTIONS AND/OR GUIDANCE ASSOCIATED WITH THIS PROJECT.~~	This note has been deleted. This note was only to be used during the "break-in" period for the Environmental Compliance plans.