




EROSION & SEDIMENT CONTROL

FIELD GUIDE

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



PLAN SYMBOLS




ISOMETRIC VIEW

** Hotspot: Monitor for sediment accumulation and remove as necessary or as directed by the engineer.*

FASTEN AT 4 PLACES,
EQUALLY SPACED


REINFORCING STRIP OVER GEOTEXTILE
FABRIC FOR UNREINFORCED SILT FENCE
(TYP. AT EACH STAKE) SEE NOTE 3.

EMBED APPROX. 12" OF GEOTEXTILE,
BACKFILL TRENCH WITH SOIL, AND
COMPACT THOROUGHLY




III. A. Silt Fence and Reinforced Silt Fence

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



NOTES:

1. THIS DEVICE IS INTENDED TO CONTROL SHEET FLOW ONLY. IT SHALL NOT BE USED IN AREAS OF CONCENTRATED FLOW.
2. SILT FENCE ENDS SHALL BE TURNED UPSLOPE TO CONTAIN RUNOFF EVERY 200-FT OR AS DIRECTED BY THE ENGINEER.
3. REINFORCING STRIP IS TO BE ONE COMPLETE STRIP COVERING ALL GEOTEXTILE FABRIC AT POST.



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.A - Maintenance

- Throughout the Project construction period, the silt fence shall be maintained by removing trapped sediment. The Contractor shall clean the geotextile of trapped sediment by tapping the geotextile when dry. No trash shall be allowed to accumulate to the height of the fence. Any geotextile that does not function due to clogging or deterioration shall be replaced.
- After every heavy rainfall, the Contractor shall check for excessive buildups of sediment which must be removed so that the silt fence can continue to function.



Flow not directed at silt fence.

** Hotspot:
Ensure use in sheet
flow conditions.*



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION




Anchor trench erosion.



Post failure.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

NOTES:

1. DIVERTED RUNOFF FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
2. DIVERTED RUNOFF FROM AN UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED STABILIZED AREA AT NON-EROSIVE VELOCITY.
3. IF TEMPORARY SWALES OR CLEAN WATER DIVERSIONS ARE TO BE OPERATIONAL FOR MORE THAN 14 DAYS, THEY SHALL BE STABILIZED IN ACCORDANCE WITH THE CONTRACT PLANS PRIOR TO BECOMING OPERATIONAL.
4. IF TEMPORARY SWALES OR CLEAN WATER DIVERSIONS ARE TO BE OPERATIONAL FOR LESS THAN 14 DAYS, THEY SHALL BE STABILIZED WITH GEOTEXTILE IN ACCORDANCE WITH THE STANDARD DETAIL, "GEOTEXTILE-LINED CHANNEL DIVERSION".

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.B - Maintenance

- Throughout the Project construction period, the Contractor shall maintain the temporary swale to the original dimensions and function of the temporary swale.
- After each rainfall, the Contractor shall check for excessive buildups of sediment which must be removed so that the temporary swale continues to function as intended. The Contractor shall remove all accumulated sediment when it reaches 50% of the height of the swale or when the accumulated sediment impedes drainage of the temporary swale, whichever comes first.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION




No stabilization. Improper swale cross section.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



PLAN SYMBOL

OUTLET AS REQUIRED
SEE NOTES 1 & 2.




PLAN

NOTES:

1. DIVERTED RUNOFF FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
2. DIVERTED RUNOFF FROM AN UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED STABILIZED AREA AT NON-EROSIVE VELOCITY.
3. IF PERIMETER DIKE SWALES ARE TO BE OPERATIONAL FOR MORE THAN 14 DAYS, THEY SHALL BE STABILIZED IN ACCORDANCE WITH THE CONTRACT PLANS PRIOR TO BECOMING OPERATIONAL.
4. IF TEMPORARY SWALES OR CLEAN WATER DIVERSIONS ARE TO BE OPERATIONAL FOR LESS THAN 14 DAYS, THEY SHALL BE STABILIZED WITH GEOTEXTILE IN ACCORDANCE WITH THE STANDARD DETAIL, "GEOTEXTILE-LINED CHANNEL DIVERSION".

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION




SECTION A-A

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.C - Maintenance

- Throughout the Project construction period, the Contractor shall maintain the perimeter dike/swale to the original dimensions and function of the swale and of the dike.
- After each rainfall, the Contractor shall check for excessive buildup of sediment that must be removed so that the perimeter dike/swale continues to function as intended. The Contractor shall remove all accumulated sediment when it reaches 50% of the height of the swale.


III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION




III.

C. Perimeter Dike/Swale

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



STABILIZE IN ACCORDANCE WITH CONTRACT PLANS PRIOR TO BECOMING OPERATIONAL. EXCAVATE TO PROVIDE REQUIRED FLOW WIDTH AT FLOW DEPTH IN ACCORDANCE WITH CHART B.

SECTION A-A

CHART B - EARTH DIKE DIMENSIONS		
SYMBOL	DIKE A (5 ac (2 ha) or less)	DIKE B (5-10 ac (2-4 ha))
a-DIKE HEIGHT	12"	18"
b-DIKE WIDTH	12"	24"
c-FLOW WIDTH	48"	72"
d-FLOW DEPTH	14"	27"

NOTES:

1. IF DESIRED, TOP WIDTH MAY BE WIDER AND SIDE SLOPES MAY BE FLATTER TO FACILITATE CROSSING BY CONSTRUCTION TRAFFC.
2. FIELD LOCATION SHOULD BE ADJUSTED AS NEEDED TO ENSURE A STABILIZED OUTFALL.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.D - Maintenance

- Throughout the Project construction period, the Contractor shall maintain the earth dike to the original dimensions and function of the channel and the dike.
- After each rainfall, the Contractor shall check for excessive buildups of sediment which must be removed so that the earth dike can continue to function as intended. The Contractor shall remove all accumulated sediment when it reaches 50% of the height of the earth dike.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



Good berm construction,


BUT



needs more vegetation.





III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION




III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

** Hotspot: Monitor pipe joints daily for damage, leakage and separation.*



SLOPE DRAIN PROFILE

(FILL FILL SLOPES)



ANTI-SEEP COLLAR PLAN

NOTES:


1. ALL TEMPORARY SLOPE DRAINS SHALL DISCHARGE INTO THE BACK OF SEDIMENT TRAPS, INTO SEDIMENT BASINS OR DITCHES DISCHARGING INTO TRAPS OR BASINS.
2. TEMPORARY SLOPE DRAINS SHALL BE USED AT THE TOP OF FILL SLOPES AS EMBANKMENT IS CONSTRUCTED, TO PREVENT EXCESSIVE EROSION UNTIL SHOULDERS ARE CONSTRUCTED AND THE SLOPES ARE SEEDDED AND MULCHED.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.E - Maintenance

- Maintenance of embankment slopes, edge berms, and interceptor berms shall conform to the requirements of Section 202.
- The drain system shall be inspected for clogging and rips or breaks and shall be cleaned and repaired as required to remain functional.

Minimize pipe joints using long sections. Anchor all joints.




III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

*Pipe supported by fill with
stable riprap outfall*



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

NOTES:

1. THE WORK SHALL CONSIST OF INSTALLING A SANDBAG DIKE FOR THE PURPOSE OF EROSION CONTROL WHEN CONSTRUCTION ACTIVITIES TAKE PLACE WITHIN THE STREAM CHANNEL SUCH AS BANK STABILIZATION OR BRIDGE ABUTMENT CONSTRUCTION.
2. THE SANDBAG DIKE SHALL BE INSTALLED AT THE UPSTREAM LOCATION FIRST.
3. THE HEIGHT OF THE SANDBAG DIKE SHALL BE 1' ABOVE THE PEAK ELEVATION OF THE ONE YEAR STORM, OR EQUAL WITH THE TOP OF BANK, WHICHEVER IS LESS. SEE PLANS FOR INFORMATION.
4. THE SPILLWAY SHALL BE SIZED TO PASS A (1) ONE YEAR STORM EVENT PEAK FLOW, SEE PLANS.
5. THE PIPE, WHEN UTILIZED, SHALL BE SIZED TO PASS THE STREAM BASE FLOW. A STABILIZED OUTFALL SHALL BE PROVIDED.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.F - Maintenance

- The Contractor shall maintain the original dimensions of the accepted sandbag dikes and sandbag diversions.

No impervious sheeting.



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



III.


F. Sandbag Dike

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION




PLAN SYMBOL

1" REBAR FOR BAG
REMOVAL FROM INLET




GEOTEXTILE INLET INSERT

EXPANSION RESTRAINT
(1/4" NYLON ROPE
W/2" FLAT WASHERS)



DUMP STRAPS, 2 EA.

INSERT CROSS-SECTION




PERSPECTIVE VIEW

NOTES:

1. ONE (1) GEOTEXTILE INLET INSERT SHALL BE INSTALLED PER GRATE OPENING.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

COVER CURB OPENING(S) WITH FOAM INSERTS OR OTHER APPROVED MEANS




NOTES:

PERSPECTIVE VIEW


CURB INLET SEDIMENT CONTROL SHALL ONLY BE USED WHEN DRAINAGE INLET SEDIMENT CONTROL CANNOT BE USED. EX. PARTIALLY COMPLETED STREETS, PAVED AREAS.

EXPANSION RESTRAINT
(1/4" NYLON ROPE
W/2" FLAT WASHERS)



DUMP STRAPS,
2 EA.


INSERT CROSS-SECTION



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.G - Maintenance


- Throughout the Project construction period, the inlet sediment controls shall be maintained and remain functional. Maintenance shall include cleaning the geotextile of trapped sediment by tapping the geotextile when it is dry. After every rainfall, the Contractor shall inspect the inlet sediment control. The geotextile insert shall be replaced when 50% of the voids are clogged. Any geotextile that does not function due to clogging or deterioration shall be replaced.



Inlet throat not blocked.

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

Positive drainage to insert
not provided.



Should be using DRAINAGE INLET
PROTECTION (III. I)


No insert.



III.


G. Curb Inlet Sediment Control

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



III. H. Curb Inlet Sediment Control (Alternate)

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION




PLAN SYMBOL

WIRE MESH, 1/2" X 1/2" 19 GAGE


** Hotspot: Monitor geotextile and mesh for damage and excess (more than 1/3 of height) sediment.*

GEOTEXTILE



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

IF THE INLET IS NOT AT LOW POINT, INSTALL SEDIMENT CONTROL
EARTH DIKE (III. D) DOWNSTREAM FROM INLET.



SECTION A-A

III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

III.H - Maintenance

- Throughout the Project construction period, the inlet sediment controls shall be maintained and remain functional. Maintenance shall include cleaning the geotextile of trapped sediment by tapping the geotextile when it is dry. After every rainfall, the Contractor shall inspect the inlet sediment control. Any geotextile that does not function due to clogging or deterioration shall be replaced.
- The Contractor shall remove all accumulated sediment from around the drainage inlet sediment control when the sediment has reached 6" (150 mm) from the top of the geotextile.



Sediment removed.



III. PERIMETER CONTROLS, DIVERSIONS AND INLET PROTECTION

- When the sediment has reached 50% of the height of the curb, the Contractor shall remove all accumulated sediment from around the curb inlet sediment control.

No framing, wrong geotextile.

