



NOTES:

- 1). ALL W-BEAMS ARE $13'-6\frac{1}{2}"$ IN LENGTH.
- 2). PLACE GUARDRAIL DELINEATORS IN ACCORDANCE WITH DETAIL B-13, SHEET 9.
- 3). POSTS 1, 2, 9, & 10 ARE TO BE W6x9, 6'-0" STEEL POSTS. POSTS 3 THROUGH 8 ARE TO BE TYPE 31 LONG, WOOD BREAKAWAY POSTS.
- 4). THE RAIL SHALL BE ATTACHED AT POSTS 3 THROUGH 8 WITH A $\frac{5}{8}$ " x 22" GUARDRAIL BOLT, STEEL WASHER, AND RECESS NUT.
- 5). CULVERT HEADWALL SHALL NOT EXTEND MORE THAN 2" ABOVE GRADE.
- 6). THERE SHALL BE A MINIMUM OF 12" FROM THE BACK OF POST TO THE CULVERT WINGWALLS.
- 7). IF CURB IS USED, IT SHALL BE A MAX 2" HEIGHT WITHIN THE LIMIT OF PAYMENT OF THE GUARDRAIL OVER CULVERT.
- 8). MASH COMPLIANT SYSTEM FHWA ELIGIBILITY LETTER B-189



MGINEERING SUPPORT DATE

RECOMMENDED

STANDARD NO.

GUARDRAIL OVER CULVERTS, TYPE 3-31

B-3 (2020)

SHT. 3

OF 3

APPROVED

REVIEWED

Y DIRECTOR - DESIGN

09/01/2020

09/01/2020 DATE