

LOOP DETECTOR LEAD-IN WIRE INSTALLATION

NOTES:

- ALL SAWCUTS SHALL BE A DEPTH OF 3½" ON ALL SURFACES.
 CONTRACTOR SHALL INSTALL LEAD-IN WIRE IN THE MOST DIRECT ROUTE TO THE JUNCTION WELL USING THE CLOSEST CONCRETE CURB JOINT.
- 3). ALL SAWCUTS SHALL BE PATCHED WITH NON-SHRINK CONCRETE CAULK.
 4). CONTRACTOR SHALL CORE AT FULL DEPTH OF SAWCUT, 3 ½".

	LOOP DETECTOR LEAD-IN WIRE INSTALLATION - JUNCTION WELL IN CONCRETE ISLAND							REVIEWED	DEPUTY DIRECTOR - DESIGN	09/01/2020 DATE
V DeIDOT <u></u>	RECOMMENDED	STANDARD NO.	T-8 (2020)	SHT.	3	OF	4	APPROVED	CHIEF ENGINEER	09/01/2020 DATE