



NOTES:

- 1). FOR OMITTING ONE POST, SEE DETAIL B-1, SHEET 4.
- 2). PLACE GUARDRAIL DELINEATORS IN ACCORDANCE WITH DETAIL B-13, SHEET 9.
- 3). POSTS 1 & 8 ARE TO BE W6x9, 6'-0" STEEL POSTS. POSTS 2 THROUGH 7 ARE TO BE TYPE 31 LONG, WOOD BREAKAWAY POSTS.
- 4). THE RAIL SHALL BE ATTACHED AT POSTS 2 THROUGH 7 WITH A $\,\%''$ x 22" GUARDRAIL BOLT, STEEL WASHER, AND RECESS NUT.
- 5). WHERE THE HEADWALL PROJECTION IS LESS THAN 2" ABOVE GRADE, THE BACK OF THE CRT POST MAY BE ALIGNED WITH THE NEAR SIDE OF THE HEADWALL.
- 6). WHERE THE STRUCTURE PROJECTION IS GREATER THAN 2" ABOVE GRADE, THE INSIDE FACE OF THE HEADWALL SHALL BE A MINIMUM OF 8'-0" FROM THE FACE OF THE W-BEAM.
- 7). PROVIDE AT LEAST 50'-0" OF TYPE 1-31 GUARDRAIL, INCLUDING END ANCHORAGE, TO ENSURE INTENDED FUNCTION
- 8). PROVIDE AT LEAST 37'-6" OF TANGENT 1-31 GUARDRAIL BEFORE INTRODUCING GUARDRAIL FLARES IN ACCORDANCE WITH THE RATES SHOWN IN STANDARD DETAIL B-1, SHEET 1 TO ENSURE INTENDED FUNCTION.
- 9). IF CURB IS USED, IT SHALL BE A MAX 2" HEIGHT WITHIN THE LIMIT OF PAYMENT OF THE GUARDRAIL OVER CULVERT.
- 10). MASH COMPLIANT SYSTEM FHWA ELIGIBILITY LETTER B-189.

