

1). INSTALLATION OF EQUIPMENT BETWEEN SERVICE PEDESTAL AND LIGHTING/CONTROLLER CABINET SHALL BE AS PER CONTRACT DRAWINGS/DETAILS.

2). SEE DETAIL T-15, SHEET 1, FOR SIGN POST AND BREAKAWAY ASSEMBLY DETAILS.

3). ATTACH ALUMINUM PANEL TO SIGN POSTS WITH (6) $^{5}\!_{16}$ " x $2^{1}\!_{2}$ " LONG GRADE 5 BOLTS, FLAT WASHERS, AND NYLON LOCK NUTS, 3 ON EACH SIDE.

4). MOUNT METER SOCKET TO ALUMINUM PANEL WITH (4) $\frac{5}{16}$ x $\frac{3}{4}$ " STAINLESS STEEL BOLTS AND NYLON LOCK NUTS.

5). MOUNT CIRCUIT BREAKER BOX TO ALUMINUM PANEL WITH (4) 5/16" x 3/4" STAINLESS STEEL BOLTS AND NYLON LOCK NUTS.

6). ALL CONDUITS AND OTHER ASSOCIATED PIECES SHALL BE 2" RIGID GALVINIZED CONDUIT UNLESS SPECIFIED DIFFERENTLY ON THE PLANS OR BY LOCAL UTILITY COMPANY. ALL

CONDUITS SHALL BE INSTALLED FROM ENCLOSURE TO TYPE 1 JUNCTION WELL. JUNCTION WELL SHALL BE PLACED WITHIN 10' OF SERVICE PEDESTAL (OR PER PLAN).

7). CONCRETE COLLAR SHALL CONTAIN 25 LBS OF CONCRETE AT EACH LEG JUST BELOW GRADE AS DIRECTED BY INSPECTOR.

8). GROUND ROD SPREAD SHALL BE TWICE THE LENGTH OF THE GROUND ROD.

VIEWED)
--------	---

12/16/2022 DEPUTY DIRECTOR - DESIGN DATE 12/21/2022 CHIEF ENGINEER DATE

12/13/2022